

Comparison of Eden Park Schemes

	Original Scheme	Baseline Scheme	Enhanced Scheme
Cost	\$385M	\$197M	\$241.5M
RWC 2011 Capacity	60,000	60,000	60,000
Post-RWC capacity (permanent seats)	60,000	54,000	50,000
South stand height	38.5 m	34.62 m	34.62 m
South Stand distance from street	27.82 m	34.8 m	34.8 m
Covered seats in South Stand	17,900	15,085	16,898
Corporate boxes	52	52	52
East Stand height	28 m	15m	19.22 m
East Stand distance from street	6.8 m	At boundary (Current Terraces)	12.5 m
Covered seats in East	8,800	3,279 Panasonic Stand	1,200
Corporate boxes	None	None	None
Internal concourses / internalisation of pedestrian movement	Yes	No	Yes
No. 2 Ground	Replaced with Transport centre	Retained for cricket	Retained for cricket
Transport hub and infrastructure to support shift to public transport	Yes	Yes	Yes